SCOPE OF WORK

1. Work will be done as per attached **BOQ**.

2. Duration of work shall be 15 days after issuance of Letter to Proceed.

3. HSE manual shall be followed and appropriate PPE shall be used by workers.

4. Location of work is "Basement, SSGC Head Office, Gulshan-e-Iqbal, Sir Shah Suleman Road, Karachi".

5. Details of POC for tender is following:

   Name: Muhammad Faizan Rajput, Engineer (Services)

   Contact# 021-99021032

   Name: Rana Danish, Engineer (Services)

   Contact# 021-99013264

SPECIAL TERMS & CONDITIONS

1. Bidder must visit location before submission of quotation.

2. Bidder must be registered in PEC with Specialization Code EE-02.

3. Bidder must submit at least 03 Completion Work Certificates of similar nature work along with Quotation.

4. Incomplete bid will be rejected.

5. Minimum 5 Years established business in Security & Surveillance.

6. Payment will be made on the basis of actual work done.

7. The bidder must fill and submit attached detailed BOQ with quotation.

BOQ

S. No.	Description of Work	UOM	Qty	Unit rate	Total
1	Services required for setting up Network Video Recorder with HDD. (HDD provided by SSGC)	Job	01		
2	Services required for Installation of network bullet cameras along Weather proof Back Box 4"x4" (Camera provided by SSGC).	Lot	09		
3	Services required for Installation of PoE Network Switches with Media Convertor and 4U equipment Rack. (Switches & Media Convertor provided by SSGC)	Lot	03		
4	Services required for setting up of Display Screen with 15 meter HDMI Cable. (LCD provided by SSGC)	Lot	01		
5	Services required for Laying of Cat-6 Cable in UPVC Pipe 1" dia along required accessories. (Cable provided by SSGC)	meter	230		
6	Services required for Laying of Fiber Optic Cable in UPVC Pipe 1" dia along required accessories. (Cable provided by SSGC)	meter	350		
7	Services required for Fiber Optic Cable Splicing.	Job	06		
8	Testing and commissioning of Complete installation.	Job	01		

Total .... Rs. _____/=